

Nuclear Emergency Hose Deployment Modules


7-Compartment Rolled Hose Main Module







Hose Reel Storage Module 8-Modules

United States Nuclear Regulatory Commission









FEATURES


3" x 3" x .25" Extruded Aluminum Tube Frame
Welded Frame
.125" Plate Floors & Panels
Welded Floors
Bolted Top & Side Panels
Manual Re-Wind Reels
Solid Steel Shafts
Pillow Block Bearings
Hinged Hose Deployment Panels
"D" Ring Closures
No Tools Needed Operation
84" Wide x 123" Long x 56.50" Tall
ISO Corners
Lifting Eyes



TRANSPORTABLE Truck / Trailer Fixed Wing Aircraft Rotory Wing Aircraft Fork Lift




CONTAINER WEIGHT: 6845 lbs.



HOSE LOAD 600' x 1.5" UHP Hose 200' x 2.5" Suction Hose 2-Manual Hand Cranks



APPROVED



Back View Main Module

FEATURES

3" x 3" x .25" Extruded AluminumTube Frame
Welded Frame
.25" Plate Floors & Panels
Welded Floors & Panels
Pan Style Compartment Access Doors
"D" Ring Closures
Bolted Top Sections
84" Wide x 123" Long x 96" Tall
ISO Corners
Lifting Eyes
Fork Lift Pockets

HOSE LOAD

48-Sections of 50' x 5" Supply Line 9-Sections of 100' x 2.5" Supply Line 24-Sections of 10' x 6" HSH

